# BRUHATH BENGALURU MAHANAGARA PALIKE

**Yelahanka Division, Yelahanka Zone**

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64

## APPROVED SCHEDULE –'B'

Name of Work:- Providing cement concrete road and drain and culverts in AK Colony at Doddabettahalli layout surrounding areas in Ward No. 03 Attur

| Sl | Description | Unit | Approved Qty | Approved Rate Technical Manager (West) KRIDL, BBMP, | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 1 | KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 (P.No-143, I.No-19.1) | Cum | 1404.32 | 215.28 | Rupees Two Hundred Fifteen and Paise Twenty Eight Only |
| 2 | KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222 I.No-27.18) | Cum | 171.07 | 5421.90 | Rupees Five Thousand Four Hundred Twenty One and Paise Ninety Only |
| 3 | Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW. P&IWTD S.R 2018-19) | Cum | 355.23 | 7070.20 | Rupees Seven Thousand Seventy and Paise Twenty Only |

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

| | Description | Unit | Approved Qty | Approved Rate Technical Manager (West) KRIDL, BBMP, | |
|---|---|---|---|---|---|
| | | | | Rate | Rate in Words |
| 4 | KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWTD S.R 2018-19) | Ton | 25.87 | 73992.24 | Rupees Seventy Three Thousand Nine Hundred Ninety Two and Paise Twenty Four Only |
| 5 | Providing and fixing RCC precast cover slab of 100mm thick for drain in cement concrete 1:1.5:3 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate) | Sqm | 775.20 | 2337.00 | Rupees Two Thousand Three Hundred Thirty Seven Only |
| 6 | Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, | Nos | 342.00 | 432.48 | Rupees Four Hundred Thirty Two and Paise Forty Eight Only |
| 7 | Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6. (P.No.180, I.No.24.1 of PW, P&IWTD SR 2018-19) | Sqm | 61.60 | 84.80 | Rupees Eighty Four and Paise Eighty Only |
| 8 | Providing and fixing RCC precast cover slab of 250mm thick made out of CC 1:2:4 and jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate) | Sqm | 75.60 | 5418.00 | Rupees Five Thousand Four Hundred Eighteen Only |

Signature of the Contractor

EXECUTIVE ENGINEER-4
YELAHANKA DIVISION
BENGALURU-560 010

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.